



**Notice of Revised Pedernales Electric Cooperative Specifications
Posted December 3, 2021**

Underground Installation Specifications

- 530-034: 3Ø Transformer Pad 2000–3000 kVA
 - Revised one side of primary conduit phases from R B Y to Y B R

- 560-052: 600-Volt Underground Service From Overhead Transformer
 - Added concrete to both conduit sweeps